

REL.	NO.	QTY	BY G.C.		ITEM DESCRIPTION	MFR. & MODEL NUMBER	PLUMB	ELECT	GAS	REMARKS	NO.
			SUPPLY	INST.							
					<b>B MISCELLANEOUS BUILDING ELEMENTS</b>						
	B2-001	SEE REMARKS	X	X	FIRE EXTINGUISHER	SENTRY OR EQUAL				VERIFY TYPE, QUANTITY AND LOCATION OF ALL FIRE EXTINGUISHERS WITH FIRE MARSHAL	B2-001
	B3-001	1		X	GRAB BAR 1-1/2" DIA. x 18" S.S. FIN.	BOBRICK #B-B6806X18				SURFACE MTD.	B3-001
	B3-003	1		X	GRAB BAR 1-1/2" DIA. x 36" S.S. FIN.	BOBRICK #B-B6806X36				SURFACE MTD.	B3-003
	B3-004	1		X	GRAB BAR 1-1/2" DIA. x 42" S.S. FIN.	BOBRICK #B-B6806X42				SURFACE MTD.	B3-004
	B4-002	1		X	MIRROR 18"x36"	BOBRICK #B-165 1836					B4-002
	B5-004	3		X	PAPER TOWEL DISPENSER	GEORGIA-PACIFIC #59010					B5-004
	B7-001	1		X	SANITARY NAPKIN DISPOSAL	RUBBERMAID #6140				SURFACE MTD	B7-001
	B8-001	3		X	SANITIZER DISPENSER	KAY CHEMICAL #3741					B8-001
	B11-001	3		X	SOAP DISPENSER (WALL MOUNT)	KAY CHEMICAL #3741				SURFACE MTD	B11-001
	B12-003	2		X	SPLASH GUARD FOR HAND SINK (9"x19")	AERO UNIVERSAL SIDE SPLASH					B12-003
	B13-001	1		X	STAINLESS STEEL 3-COMP/DISHWASH/CLEAN DISH WALL PANEL	CAPTIVEAIRE, INC.				CUSTOM SIZE	B13-001
	B13-002	1		X	STAINLESS STEEL PANEL PKG. FOR FRYER WALL	CAPTIVEAIRE, INC.				CUSTOM SIZE	B13-002
	B13-003	1		X	STAINLESS STEEL PANEL PKG. FOR OVEN WALL	CAPTIVEAIRE, INC.				CUSTOM SIZE	B13-003
	B14-001	1	SEE SHEET E1	SEE SHEET E1	SWITCHGEAR PACKAGE			X		INCLUDES BRANCH PANELS	B14-001
	B15-002	1		X	TOILET PAPER DISPENSER	BRIGHTON PROFESSIONAL #376447				SURFACE MTD.	B15-002
	B18-001	2		X	WASTE BASKET - 32 GALLON	RUBBERMAID #2632 (GRAY)				(NOT SHOWN ON PLAN)	B18-001
	B18-002	2		X	DOLLY FOR WASTE BASKET - 32 GALLON	RUBBERMAID #2640				(NOT SHOWN ON PLAN)	B18-002
	B18-003	4		X	WASTE BASKET	WASSERSTROM SLIM JIM #3541 (GRAY)				(NOT SHOWN ON PLAN)	B18-003
	B19-001	1		X	DUNNAGE RACK USED AS WATER HEATER STAND	NEW AGE #98147				30" x 8" x 30" WITH ADJUSTABLE FEET	B19-001
					<b>C COOKING EQUIPMENT</b>						
	C2-002	1		X	HIGH EFFICIENCY DOUBLE OPEN FRYER	PITCO		X	X		C2-002
	C3-042	1		X	XLTD DOUBLE PIZZA OVEN, HIGH PERFORMANCE	XLTD #3255 H-SERIES		X	X		C3-042
					<b>E EXHAUST HOODS/FIRE SUPP.</b>						
	E2-005	1		X	FRYER HOOD 48"	CAPTIVEAIRE, INC.	X	X		SEE HOOD MFR. DRAWINGS	E2-005
	E3-006	1		X	S.S. OVEN HOOD (9'-0" HOOD LENGTH)	CAPTIVEAIRE, INC.		X		SEE HOOD MFR. DRAWINGS	E3-006
					<b>F OFFICE/EMPLOYEE/MUSIC/MISC.</b>						
	F2-002	1		X	BULLETIN BOARD (36"x24")	WASSERSTROM #6021089				(NOT SHOWN ON PLAN)	F2-002
	F3-003	4		X	LOBBY CHAIR	FCI-FACILITY CONCEPTS INC., PH#CH01-W				METAL CHAIR WITH WOOD SEAT AND STEEL FRAME.	F3-003
	F4-001	1			DELIVERY DRIVER MAP	TBD					F4-001
	F5-003	1		X	FILE CABINET	HON #312CPL, PF68975				PLACE UNDER MANAGERS DESK	F5-003
	F6-001	1		X	FIRST AID KIT	SWIFT #68-UFPC					F6-001
	F7-002	2		X	FLOOR MAT 3' X 5' CHARCOAL	ENTRANCE INC. #3X5 ENT					F7-002
	F10-003	1		X	BLACK ROUND STOOL WITH BACKREST	GRAINGER #5NWH8				PADDED SEAT MATERIAL, UNASSEMBLED.	F10-003
	F11-001	1			PH OFFICE COMPUTER			X		POS PROVIDED	F11-001
	F12-001	1			PH MONITOR-OFFICE			X		POS PROVIDED	F12-001
	F13-001	1			OFFICE PRINTER/ COPIER/ FAX/ SCANNER			X		POS PROVIDED	F13-001
	F14-001	1		X	SAFE	CSS #CS2820-SG1TD9-RCH3					F14-001
	F15-002	3			WALL TELEPHONE						F15-002
	F18-001	1			TELEPHONE SYSTEM						F18-001
	F19-001	1			PH UPS			X			F19-001
	F20-001	1		X	LICENSE FRAME,						

REL	NO.	QTY	BY G.C.		ITEM DESCRIPTION	MFR & MODEL NUMBER	PLUMB	ELECT	GAS	REMARKS	NO.
			SUPPLY	INST.							
					<b>L LIGHT BOXES/ MISC. SIGNAGE/MENUBOARDS</b>						
	L3-010	1		X	MENU MAT	GRAPHICS SYSTEMS, INC.					L3-010
	L4-002	1		X	HAND WASH SIGN	GRAPHICS SYSTEMS, INC.				MOUNT 60" A.F.F. TO CENTERLINE OF SIGN	L4-002
	L4-005	1		X	NO DELIVERIES AFTER 11:00 AM SIGN	GRAPHICS SYSTEMS, INC.					L4-005
	L4-007	1		X	SECURITY DOOR DANGER SIGN	ADVERCO #ADVCUSTOM				ORDERS DIRECT FROM YRSF	L4-007
	L4-010	2		X	EMPLOYEE HAND WASH SIGN FOR KITCHEN	TRAEX #4530					L4-010
	L4-011	1		X	NO SMOKING SIGN	TRAEX #4513				(VERIFY LOCATION WITH NPC CM)	L4-011
	L5-007	1		X	ADA RESTROOM SIGN - UNISEX	VISUAL GRAPHIC SYSTEMS INC. #AD-117-REST-UNISEX-(P2H)				MOUNT 60" MAX. A.F.F. MEASURED FROM THE BASE LINE OF THE HIGHEST TACTILE CHARACTER.	L5-007
	L6-008	1			STORE NUMBER, STORE HOURS, SECURITY DETAIL SIGNAGE	BIG IMAGE GRAPHICS, INC.					L6-008
	L6-032	1			AMERICAS FAVORITE PANEL	BIG IMAGE GRAPHICS, INC.				CENTERED ON BULKHEAD	L6-032
	L6-034	1			SUPPLEMENTAL ARTWORK - DRINK "A"	BIG IMAGE GRAPHICS, INC.					L6-034
	L6-035	1			SUPPLEMENTAL ARTWORK - PIZZA LIGHT "B"	BIG IMAGE GRAPHICS, INC.					L6-035
	L6-036	1			SUPPLEMENTAL ARTWORK - ARCADE "C"	BIG IMAGE GRAPHICS, INC.					L6-036
					<b>P FOOD PREPARATION</b>						
	P2-001	1		X	"E" PIZZA HUT MAKE TABLE W/ SLIDING LID	RANDELL #PH120 E	X	X			P2-001
	P3-003	1		X	2-COMP PROOFER	TRAUlsen #RPP232L-FHS		X			P3-003
	P5-001	1		X	SHORTENING SHUTTLE	AERO #SSA-925				(NOT SHOWN ON PLAN)	P5-001
					<b>R REFRIGERATION</b>						
	R2-009	1		X	SLIDING DOOR VISICOOLER - FULL HEIGHT	VISICOOLER		X		(PROVIDED BY PEPSI)	R2-009
	R3-010	1		X	UNDER COUNTER WS WORKTOP FREEZER (RH)	DELFIELD #403-WS1		X		SPECIFY RIGHT HAND WHEN ORDERING.	R3-010
	R4-012	1		X	1-DOOR WINGSTREET REFRIGERATOR (RH)	BEVERAGE-AIR #UCF20		X		DOOR HINGING IS INTERCHANGEABLE. MOUNTED ON SHELF AT WINGSTREET PREP STATION.	R4-012
					<b>S SERVING/PICK-UP</b>						
	S15-003	1		X	HOT HOLDING CABINET - PASS-THRU	WINSTON #HA4522Z	X	X		DOOR HINGING IS INTERCHANGEABLE ON PASS-THRU UNIT	S15-003
	S25-001	1		X	TICKET STRIP (30" LENGTH)	SAN JAMAR #CK6530A					S25-001
	S25-002	2		X	TICKET STRIP (36" LENGTH)	SAN JAMAR #CK6536A					S25-002
					<b>U SECURITY/COMM./FIRE PROT./POS</b>						
	U1-001	1		X	BCO - BACK CASH OUT TERMINAL, CASH DRAWER			X			U1-001
	U1-001A	1		X	BCO - BACK CASH OUT TERMINAL			X			U1-001A
	U1-002	2		X	FCO - FRONT CASH OUT TERMINAL, CASH DRAWER, CREDIT CARD SWIPE			X			U1-002
	U1-004	2		X	ORDER ENTRY TERMINAL			X			U1-004
	U1-005	1		X	KITCHEN MONITOR			X			U1-005
	U1-006	2		X	KITCHEN MONITOR W/ WALL BRACKET SUPPORT			X			U1-006
	U1-007	3		X	KITCHEN RECEIPT PRINTER			X			U1-007
	U1-008	1		X	SUS TICKET PRINTER			X			U1-008
	U1-009	1		X	CUSTOMER CASH OUT MONITOR			X			U1-009
					<b>W WALK-IN COOLERS/FREEZERS</b>						
	W1-001	1		X	WALK-IN COOLER (9'-6" O.A.H.)	TBD	X	X		REFRIGERATION INSTALLATION MUST BE PERFORMED BY AN ICS OR KOLPACK CERTIFIED SERVICE TECHNICIAN INSTALLATION CONTRACTOR TO PROVIDE WALK-IN UNIT REFRIGERATION PIPING AND INSULATION. SEE HVAC GENERAL NOTE #46 ON SHEET M5	W1-001
	W1-002	1		X	WALK-IN FREEZER (9'-6" O.A.H.)	TBD	X	X		REFRIGERATION INSTALLATION MUST BE PERFORMED BY AN ICS OR KOLPACK CERTIFIED SERVICE TECHNICIAN INSTALLATION CONTRACTOR TO PROVIDE WALK-IN UNIT REFRIGERATION PIPING AND INSULATION. SEE HVAC GENERAL NOTE #46 ON SHEET M5	

## A2.1